


April 2018 Update Pack



Dear Colleague,

Thank you for subscribing to receive updates to the Part E Robust Details Handbook.

In this update pack, we have included a new floating floor treatment option for the generic timber separating floors E-FT-1, E-FT-2 and E-FT-3 and the steel joisted floor E-FS-2. Significantly, Collecta's HiDECK Structural system overcomes the thermal resistance issues of the standard FFT1 to allow underfloor heating to now be used with these floors.

Also of note is that the horizontal cavity stop used behind cladding systems on E-FC-18 RC Frame floor, has now been approved and specified in a way that aids drainage of the cavity; and E-FC-1 now has the option to include a membrane below the screed layer should this be required.

Other amendments include the options to Use Collecta's MICRO 15 and MICRO 50 in place of mineral wool on a number of timber and steel joisted floors; and an updating of product names on Thermal Economics' floors.

Please update your January 2018, 4th Edition Handbook as follows:

1. Remove and replace **just page 11/12** of the Introduction.
2. Remove and replace **all pages** of E-WS-5.
3. Remove and replace **all pages** of E-FC-1; E-FC-4; E-FC-12 and E-FC-14.
4. Remove and replace **just page 1/2** of E-FC-18.
5. Remove and replace **all pages** of E-FT-1; E-FT-2 and E-FT-3.
6. Remove and replace **just page 1/2** and **page 5/6** of E-FT-5.
7. Remove and replace **all pages** of E-FS-2.
8. Remove and replace **all pages** of Appendix A3.

Yours sincerely

A handwritten signature in black ink, appearing to read 'John Thompson', written over a horizontal line.

John Thompson

Chief Executive,
Robust Details Limited



Changes to the fourth edition following April 2018 update

Section	Page	Amendment
Introduction		
Table 7	12	Collecta HiDECK Structural added.

Separating Wall – Steel

E-WS-5

Diagrams 1-4	2-5	Diagrams reordered by junction type rather than by external treatment. External cladding option redefined.
--------------	-----	---

Separating Floor – Concrete

E-FC-1

Direct applied screed	1	Direct applied screed box added referencing under-screed membrane.
Checklist	6	Item 5 revised to include reference to under-screed membrane.

E-FC-4

All	1-6	Resilient layer descriptor updated to reflect change in product name.
-----	-----	---

E-FC-12

All	1-6	Resilient layer descriptor updated to reflect change in product name.
-----	-----	---

E-FC-14

All	1-6	Resilient layer and flanking strip descriptors updated to reflect change in product names.
-----	-----	--

E-FC-18

Under-screed resilient layers	1	Thermal Economics resilient layer and flanking strip descriptors updated to reflect change in product names.
Diagram 1	2	External cladding option redefined. Partial cavity closer option added.

Section	Page	Amendment
---------	------	-----------

Separating Floor – Timber

E-FT-1

Isometric	1	Collecta MICRO 50 option added.
DO box	1	Min. quilt thickness removed from point 1.
Diagram 6	5	Collecta MICRO 15 option added to FFT1. Reference added to Collecta HiDECK in Appendix A3.
Checklist	6	Item 2 & 6 amended to “specified” quilt.

E-FT-2

Isometric	1	Collecta MICRO 50 option added.
DO box	1	Min. quilt thickness removed from point 1.
Diagram 6	5	Reference added to Collecta HiDECK in Appendix A3.
Checklist	6	Item 2 & 7 amended to “specified” quilt.

E-FT-3

Isometric	1	Collecta MICRO 50 option added.
DO box	1	Min. quilt thickness removed from point 2.
Diagram 10	7	Collecta MICRO 15 option added to FFT1. Reference added to Collecta HiDECK in Appendix A3.
Checklist	8	Item 4 & 8 amended to “specified” quilt.

E-FT-5

Isometric	1	Collecta MICRO 50 option added.
Checklist	6	Item 7 amended to “specified” quilt.

Separating Floor – Steel

E-FS-2

Isometric	1	Collecta MICRO 50 option added.
DO box	1	Min. quilt thickness removed from point 1.
Diagram 3	3	Collecta MICRO 50 option added.
Diagram 6	5	Collecta MICRO 15 option added to FFT1. Reference added to Collecta HiDECK in Appendix A3.
Checklist	6	Item 2 & 6 amended to “specified” quilt.

Appendix A3

Content	1	Collecta HiDECK Structural floor board floating floor treatment added.
Collecta HiDECK Structural floor board	4	New proprietary floating floor treatment system added.

Introduction

Table 6b – Robust Detail separating floors which can be used together with the proprietary flanking constructions contained in Appendix A2

		BRIDGESTOP® system	Smartroof system	Kingspan TEK	Prestoplan PresPeak 60	Wall Cap RDA2	RoofSpace I-Roof	Space4 system
Concrete floors	E-FC-1					✓		
	E-FC-2							
	E-FC-4					✓		
	E-FC-5					✓		
	E-FC-6					✓		
	E-FC-7					✓		
	E-FC-8					✓		
	E-FC-9					✓		
	E-FC-10					✓ see note 1		
	E-FC-11					✓		
	E-FC-12					✓		
	E-FC-13					✓		
	E-FC-14					✓		
	E-FC-15					✓		
	E-FC-16					✓		
	E-FC-17					✓		
	E-FC-18							
	Timber floors	E-FT-1					✓	
E-FT-2						✓		
E-FT-3						✓		
E-FT-4						✓		
E-FT-5						✓		
E-FT-6						✓		
E-FT-7						✓		
E-FT-8						✓		
Steel-concrete and steel floors	E-FS-1							
	E-FS-2					✓		
	E-FS-3					✓		

Key


1 Applies only to loadbearing masonry constructions.

Introduction

Table 7 – Robust Detail separating floors which can be used together with alternative products contained in Appendix A3


		British Gypsum GypFloor	Insumate insulation tray	Collecta HiDECK Structural
Concrete floors	E-FC-1	✓		
	E-FC-2	✓		
	E-FC-4			
	E-FC-5			
	E-FC-6			
	E-FC-7	✓		
	E-FC-8			
	E-FC-9			
	E-FC-10			
	E-FC-11			
	E-FC-12			
	E-FC-13			
	E-FC-14			
	E-FC-15			
	E-FC-16			
	E-FC-17			
	E-FC-18			
	Timber floors	E-FT-1		✓
E-FT-2			✓	✓
E-FT-3			✓	✓
E-FT-4				
E-FT-5				
E-FT-6				
E-FT-7			✓	
E-FT-8			✓	
Steel-concrete and steel floors	E-FS-1	✓		
	E-FS-2			✓
	E-FS-3			

- Twin metal frames
- Use with reinforced concrete frame construction only
- Concrete slabs with flat soffits only - no profiled decking



Wall lining	- 2 or more layers of gypsum-based board (minimum total nominal mass per unit area 20 kg/m ²) both sides - all joints staggered
Steel frame	60mm (min) studs both sides
Wall width	230mm (min) between inner faces of wall linings, or 190mm (min) where service zones are used (see Section 6)
Absorbent material	One layer 75mm (min) unfaced mineral wool batts (density 10-40 kg/m ³)
External (flanking) wall	See Sections 1 to 3

Alternative higher-performance wall constructions (see Section 12)



Alternative external (flanking) wall construction

Storey height glazing units are an acceptable alternative to the cavity walls illustrated:

- glazing units should not be continuous between storeys
- mullion or transom supports/framing should not be continuous between dwellings
- the sound insulation performance is improved where the junction between the separating wall and external (flanking) wall occurs at a concrete column position

DO


- Keep wall linings at least 230mm apart, or 190mm (min) where service zones are used (see Section 6)
- Ensure the batts cover whole wall area and are fitted together correctly and not tightly compressed between twin frames
- Ensure that all cavity stops/closers are flexible or are fixed to one frame only
- Make sure there is no connection between the two frames except where ties are necessary for structural reasons
- Stagger joints in wall linings to avoid air paths
- Seal all joints in outer layer with tape or caulk with sealant
- Refer to Appendix A

Sheathing


Where required for structural or security reasons, it is permissible to apply sheathing board to one frame of the separating wall (see Section 6)

1. External (flanking) wall junction – at concrete column position

1.1 Masonry or precast external treatment




1.2 Lightweight cladding external treatment




2. External (flanking) wall junction – at large concrete column (aligned to wall or offset) or at shear wall

2.1 Masonry or precast external treatment




2.2 Lightweight cladding external treatment




*Particular care should be taken in respect of Building Regulations Part B Fire

3. External (flanking) wall junction – without concrete column

3.1 Masonry or precast external treatment





3.2 Lightweight cladding external treatment



*Particular care should be taken in respect of Building Regulations Part B Fire

4. Separating wall internal junctions


4.1 Where separating wall meets separating wall



Seal all perimeter joints with tape or caulk with sealant

Fully fill void with mineral wool quilt or batt (min 10 kg/m³)


Internal fixing angle (if required)



Plan


Ensure studs, top and bottom rails or gypsum boards do not bridge between the twin frames

4.2 Where separating wall meets lift shaft wall or other such structure



50mm (min) between studs and shear wall/lift shaft wall


Additional insulation for thermal requirements is permitted



Internal fixing angle (if required)

Fully fill void with mineral wool quilt or batt (min 10 kg/m³)

Seal all perimeter joints with tape or caulk with sealant




Plan

Inner leaf - two layers of gypsum-based board total min 20 kg/m² and 50mm (min) mineral wool (min 10 kg/m³), placed between all studs


Ensure studs, top and bottom rails or gypsum boards do not bridge between the twin frames

5. Separating wall to separating wall junction with column/shear wall

5.1 T-junction at column or shear wall




5.2 Junction offset from column or shear wall




Ensure studs, top and bottom rails or gypsum boards do not bridge between the twin frames

6. Service zone and wall options for in-line concrete columns


Option A




Option B



Option C




Option D




Ensure studs, top and bottom rails or gypsum boards do not bridge between the twin frames

7. Separating floor junction – in-situ concrete floor E-FC-18




An alternative deflection head detail is shown below

8. Slab junction (with alternative deflection head detail)




9. Ground floor junction




Section

Alternative detail with timber floating floor finish



10. Internal wall junction




Plan

Ensure studs, top and bottom rails or gypsum boards do not bridge between the twin frames

11. Services and sockets in the separating wall


11.1 Electrical sockets, switches etc



Plan

- Stagger sockets, switches, etc. on each side of the wall such that they are not positioned in opposite bays
- Provide two or more layers of gypsum-based board (total nominal mass per unit area 20 kg/m²) to enclose electrical boxes
- Fire resistant seal where required by Part B of the Building Regulations


11.2 Electrical sockets and switches in service void



Plan

- Service void using min 25mm battens or steel studs with 2 layers of gypsum board
- Service void on surface of separating wall. This is the preferred method where more than one socket, switch, etc. are close together, e.g. in a kitchen
- Studs or battens used to create the service zone should be securely fixed back to the separating wall structure

11.3 Piped services located within wall



Plan


- Provide two or more layers of gypsum-based board (total nominal mass per unit area 20 kg/m²) to enclose pipes
- Stagger services on each side of the wall such that they are not positioned in opposite bays
- Note: this detail is not applicable for SVPs or gas pipes

Ensure studs, top and bottom rails or gypsum boards do not bridge between the twin frames


12. Higher performing wall constructions

The sound insulation performance can be increased by using the following:

12.1 Full-fill option



12.2 330mm 5-board option



CHECKLIST (to be completed by site manager/supervisor)

Company:

Site:

Plot:

Site manager/supervisor:

Table with 5 columns: Ref., Item, Yes (✓), No (✓), Inspected (initials & date). Contains 8 checklist items regarding wall linings, acoustic isolation, and cavity sealing.

Notes (include details of any corrective action)


Site manager/supervisor signature

©: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public...

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Precast concrete plank ■
Screed with floating floor treatment ■



Sketch shows FFT5 type floating floor treatment and CT1 type ceiling treatment

Floating floor	See section 4 for suitable floating floor treatment
Screed	- 40mm (min) screed directly applied to plank - cement:sand or proprietary screed nominal 80 kg/m ² mass per unit area, see Appendix A
Structural floor	Precast concrete plank of 150mm (min) thickness and 300 kg/m ² (min) mass per unit area
Ceiling	See section 3 for suitable ceiling treatment


Direct applied screed

It is permissible to lay the screed over a max. 0.5mm thick membrane, if required

DO


- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure floating floor treatment is suitable and install in accordance with the manufacturer's instructions
- Install flanking strips around the perimeter of the flooring board to isolate floor from walls and skirtings
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Refer to Appendix A

1. External (flanking) wall junction



Sketch shows FFT5 type floating floor treatment and CT1 type ceiling treatment

2. Separating wall junction



Sketch shows FFT5 type floating floor treatment and CT1 type ceiling treatment

3. Ceiling treatments for E-FC-1

All ceiling treatments must be installed in accordance with the manufacturer's instructions. All ceiling joints must be sealed with tape or caulked with sealant.

The maximum load on resilient bars shall not exceed that specified in the manufacturer's instructions.

Note: the sound insulation performance of all ceiling treatments is increased if:


- 25mm (min) mineral wool quilt is placed in the ceiling void, and/or
- resilient hangers are used.

Downlighters and recessed lighting

Provided there is a minimum ceiling void of 75mm downlighters or recessed lighting may be installed in the ceiling:


- in accordance with the manufacturer's instructions
- at no more than one light per 2m² of ceiling area in each room or see Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety




CT1 – Metal ceiling system - 100mm void

- any metal ceiling system providing 100mm (min) ceiling void
- one layer of nominal 8 kg/m² gypsum-based board




CT2 – Timber battens and counterbattens

- 50 x 50mm softwood battens
- 50 x 50mm counterbattens
- one layer of 8 kg/m² gypsum-based board



CT3 – Metal ceiling system - 75mm void

- any metal ceiling system providing 75mm (min) ceiling void
- one layer of nominal 10 kg/m² gypsum-based board



CT4 – Timber battens and metal resilient bars

Only suitable for use in conjunction with 200mm (min) precast concrete floor plank of mass per unit area 300 kg/m² (min).

- 50 x 50mm softwood battens
- metal resilient ceiling bars mounted at right angles to the battens (bars must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 17\text{dB}$ and $rd\Delta L_w = 16\text{dB}$) - see Appendix E
- one layer of minimum nominal 10 kg/m² gypsum-based board


4. Floating floor treatments for E-FC-1

All floating floor treatments :

- Must achieve a minimum laboratory performance of $rd\Delta L_w = 17\text{dB}$ - see Appendix D.
- Must be installed in accordance with the manufacturer's instructions.
- Require 5mm (min) resilient flanking strips around the perimeter of the flooring board to isolate floor from walls and skirting.


d) For further guidance on floating floor treatments and flanking strips, please refer to Appendix A.

* Note - void dimensions indicated are when floor is loaded to 25 kg/m².




FFT 1 – Resilient composite deep batten system

- 18mm (min) t&g flooring board
- resilient layer must be continuous and pre-bonded to batten
- resilient composite deep battens
- ensure any services do not bridge the resilient layer
- battens may have the resilient layer at the top or the bottom




FFT 2 – Resilient cradle and batten system

- 18mm (min) t&g flooring board
- cradle and batten
- ensure any services do not bridge the resilient layer




FFT 3 – Resilient composite standard batten system

- 18mm (min) t&g flooring board
- resilient layer must be continuous and pre-bonded to batten
- resilient composite standard battens
- ensure any services do not bridge the resilient layer
- battens may have the resilient layer at the top or the bottom



FFT 4 – Resilient overlay platform floor system

- proprietary platform system inclusive of resilient layer greater than or equal to 16 kg/m² mass per unit area
- no services to be installed in floor system*




FFT 5 – Resilient overlay shallow platform floor system

- 9mm (min) t&g flooring board
- resilient layer pre-bonded to flooring board
- no services to be installed in floor system*

* Additional under floor heating layers may be incorporated within FFT4 and FFT5 provided the complete build-up, using all components, has been tested to give a minimum laboratory performance of $rd\Delta L_w = 17\text{dB}$ - see Appendix D.

5. Services – Service pipes through separating floor



Sketch shows FFT5 type floating floor treatment and CT3 type ceiling treatment

CHECKLIST (to be completed by site manager /supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are precast concrete planks 150mm (min) thick and of mass per unit area 300 kg/m ² (min)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Are inner leaves to external (flanking) walls of the correct block density?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are joints between precast concrete planks grouted?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Are precast concrete planks built into the masonry walls?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Is screed applied directly to the planks; or over a max 0.5mm thick membrane?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Has ceiling system been installed in accordance with the manufacturer's instructions (where applicable)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Are all ceiling board joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Has floating floor treatment been installed in accordance with the manufacturer's instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Have all resilient flanking strips been fitted?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are service pipes wrapped in quilt and boxed in with two layers of nominal 8 kg/m ² gypsum-based board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Notes (include details of any corrective action)


Site manager/supervisor signature

©: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Precast concrete plank ■
Screed laid on Thermal Economics 6mm Isorubber Base resilient layer ■




Sketch shows CT0 type ceiling treatment

Screed	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m ² mass per unit area
Resilient layer	6mm Isorubber Base with IsoEdge flanking strip
Structural floor	Precast concrete plank of 150mm (min) thickness and 300 kg/m ² (min) mass per unit area
Ceiling	See section 3 for suitable ceiling treatment which is dependent on floor plank depth and supporting wall density

SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **6mm Isorubber Base** (resilient layer to be laid over entire floor area with minimum 50mm overlaps)
- 2) **IsoEdge** flanking strip
- 3) All joints taped




- **IsoEdge** flanking strip to be installed at all room perimeters. See manufacturer's guidance.
- See Section 4 for acceptable installation alternatives for 40mm proprietary screeds

From 1 January 2009, Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from Thermal Economics on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

DO

- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure 6mm Isorubber resilient layer is laid over the entire floor surface and has overlapped joints of 50mm sealed with tape. On no account should the screed come into contact with the floor slab. (see Section 4 for 40mm proprietary screeds)
- Ensure 6mm Isorubber overlaps with IsoEdge flanking strip. On no account should screed come into contact with floor slab or perimeter walls
- Ensure the IsoEdge flanking strip isolates the skirting and wall linings. On no account should screed come into contact with the wall lining and skirting
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)

1. External (flanking) wall junction




Section

- Masonry outer leaf
- External wall cavity (min 50mm)
- Inner leaf (min 100mm) aggregate concrete block (1350 kg/m³ to 1600 kg/m³ or 1850 - 2300 kg/m³) or Plasmor Aglite Ultima (1050 kg/m³) or aircrete block (450-800 kg/m³)
- IsoEdge flanking strip must overlap with Isorubber resilient layer and isolate screed from perimeter walls and skirtings
- Isorubber resilient layer must have 50mm (min) overlapped joints and be sealed with tape
- Close cavity with a flexible cavity stop unless it is fully filled with mineral wool insulation
- Concrete planks must be built into walls:
 - walls must not be continuous between storeys
 - planks must not abut inner leaf
 - all voids between planks and blockwork filled with mortar or flexible sealant
- Continuous horizontal ribbon of adhesive or IsoEdge ceiling strip
- Nominal 8 kg/m² gypsum-based board or 13mm plaster

Sketch shows CT0 type ceiling treatment

2. Separating wall junction



Section

- Separating wall:
 - if using **robustdetails**® for wall - refer to Table 3a in introduction to select an appropriate Robust Detail separating wall
 - if using wall requiring pre-completion testing – seek specialist advice
- IsoEdge flanking strip
- Isorubber resilient layer to overlap IsoEdge flanking strip
- Concrete planks to be built into wall:
 - wall must not be continuous between storeys
 - planks must not abut separating wall
 - all voids between planks and blockwork filled with mortar or flexible sealant
- Continuous horizontal ribbon of adhesive or IsoEdge ceiling strip

Sketch shows CT0 type ceiling treatment

3. Ceiling treatments for E-FC-4

All ceiling treatments must be installed in accordance with the manufacturer's instructions. All ceiling joints must be sealed with tape or caulked with sealant.

Note: the sound insulation performance of all ceiling treatments is increased if:


- 25mm (min.) mineral fibre quilt is placed in the ceiling void, and/or
- resilient hangers are used.

Downlighters and recessed lighting

Provided there is a minimum ceiling void as stated below for CT0, CT1 or CT2, downlighters or recessed lighting may be installed in the ceiling:


- in accordance with the manufacturer's instructions
- at no more than one light per 2m² of ceiling area in each room or see Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety




CT0 – Metal ceiling system - 150mm void To be used for 150mm (min) depth concrete planks

- any metal ceiling system providing 150mm (min) ceiling void
- one layer of nominal 8 kg/m² gypsum-based board



CT1 – Metal ceiling system - 100mm void Only to be used for 200mm (min) depth concrete planks


- any metal ceiling system providing 100mm (min) ceiling void
- one layer of nominal 8 kg/m² gypsum-based board



CT2 – Timber battens and counterbattens with IsoSonic Hangers Type C. Only to be used for 200mm (min) depth concrete planks

- 50 x 50mm softwood battens
- 50x50mm counterbattens
- IsoSonic Hangers Type C
- one layer of nominal 8 kg/m² gypsum-based board


4. Resilient layer installation for different screed types



SCREED TYPE

65mm (min) cement:sand screed

- Isorubber joints to be overlapped by 50mm (min)
- Upper Isorubber edge joints to be sealed by tape



SCREED TYPE

40mm (min) proprietary screed


- Isorubber joints to be butt jointed
- Isorubber joints to be sealed by tape
- Polythene layer to be laid over whole floor overlapping joints

5. Underfloor heating systems within screeds


Underfloor heating systems (including connectors and fixings) installed within the screed must not penetrate the resilient layer or bridge the screed to the slab.

Underfloor heating systems which have a supporting layer/board may be laid on top of the Isorubber.

Appropriate screed depth cover to the heating system must be designed for – contact underfloor heating manufacturer for guidance.



6. Services – Service pipes through separating floor



Sketch shows CT0 type ceiling treatment

CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Has training been received from Thermal Economics?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Are precast concrete planks 150mm (min) thick and of mass per unit area 300 kg/m ² (min)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are inner leaves to external (flanking) walls of the correct block density?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Are joints between precast concrete planks grouted and sealed?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Are precast concrete planks built into the masonry walls?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Is the IsoEdge flanking strip installed for all room perimeters?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Are the Isorubber joints overlapped by 50mm and sealed with tape?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Is the Isorubber layer overlapping the IsoEdge flanking strip?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Are the skirting boards isolated from the screed by the IsoEdge flanking strip?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are all ceiling board joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Are service pipes wrapped in quilt and boxed in with two layers of nominal 8 kg/m ² gypsum-based board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>


Contact details for technical assistance from Thermal Economics, manufacturer of Isorubber resilient layer system:
Telephone: 01582 544255 Fax: 01582 429305 E-mail: technical@thermal-economics.co.uk

Notes (include details of any corrective action)

Site manager/supervisor signature

©: UK registered trade mark no. 2291665
 © Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.
 Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Precast concrete plank ■
Screed laid on Thermal Economics Isorubber HP3 resilient layer ■



Sketch shows CT1 type ceiling treatment

Screed	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m ² mass per unit area
Resilient layer	3mm Isorubber HP3 layer with IsoEdge flanking strip
Structural floor	Precast concrete plank of 150mm (min) thickness and 300 kg/m ² (min) mass per unit area
Ceiling	See section 3 for suitable ceiling treatment

SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **3mm Isorubber HP3** (resilient layer to be laid over entire floor area with minimum 50mm overlaps)
- 2) **IsoEdge** flanking strip
- 3) All joints taped

IsoEdge Flanking Strip


- **IsoEdge** flanking strip to be installed at all room perimeters. See manufacturer's guidance.
- See Section 4 for acceptable installation alternatives for 40mm proprietary screeds

From 1 January 2009, Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from Thermal Economics on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

DO


- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure 3mm Isorubber HP3 resilient layer is laid over the entire floor surface and has overlapped joints of 50mm sealed with tape. On no account should the screed come into contact with the floor slab. (see Section 4 for 40mm proprietary screeds)
- Ensure 3mm Isorubber HP3 overlaps with IsoEdge flanking strip. On no account should screed come into contact with floor slab or perimeter walls
- Ensure the IsoEdge flanking strip isolates the skirting and wall linings. On no account should screed come into contact with the wall lining and skirting
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions (where applicable)

1. External (flanking) wall junction



Sketch shows CT1 type ceiling treatment

2. Separating wall junction



Sketch shows CT1 type ceiling treatment

3. Ceiling treatments for E-FC-12

All ceiling treatments must be installed in accordance with the manufacturer’s instructions. All ceiling joints must be sealed with tape or caulked with sealant.

Note: the sound insulation performance of all ceiling treatments is increased if:


- 25mm (min.) mineral fibre quilt is placed in the ceiling void, and/or
- resilient hangers are used.

Downlighters and recessed lighting

Provided there is a minimum ceiling void as stated below for CT0, CT1 or CT2, downlighters or recessed lighting may be installed in the ceiling:


- in accordance with the manufacturer’s instructions
- at no more than one light per 2m² of ceiling area in each room or see Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety




CT0 – Metal ceiling system - 150mm void To be used for 150mm (min) depth concrete planks

- any metal ceiling system providing 150mm (min) ceiling void
- one layer of nominal 8 kg/m² gypsum-based board



CT1 – Metal ceiling system - 100mm void Only to be used for 200mm (min) depth concrete planks


- any metal ceiling system providing 100mm (min) ceiling void
- one layer of nominal 8 kg/m² gypsum-based board



CT2 – Timber battens and counterbattens with IsoSonic Hangers Type C. Only to be used for 200mm (min) depth concrete planks

- 50 x 50mm softwood battens
- 50x50mm counterbattens
- IsoSonic Hangers Type C
- one layer of nominal 8 kg/m² gypsum-based board


4. Resilient layer installation for different screed types



SCREED TYPE

65mm (min) cement:sand screed

- Isorubber joints to be overlapped by 50mm (min)
- Upper Isorubber edge joints to be sealed by tape



SCREED TYPE

40mm (min) proprietary screed


- Isorubber joints to be butt jointed
- Isorubber joints to be sealed by tape
- Polythene layer to be laid over whole floor overlapping joints

5. Underfloor heating systems within screeds


Underfloor heating systems (including connectors and fixings) installed within the screed must not penetrate the resilient layer or bridge the screed to the slab.

Underfloor heating systems which have a supporting layer/board may be laid on top of the Isorubber.

Appropriate screed depth cover to the heating system must be designed for – contact underfloor heating manufacturer for guidance.



6. Services – Service pipes through separating floor



Sketch shows CT1 type ceiling treatment

CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Has training been received from Thermal Economics?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
2.	Are precast concrete planks 150mm (min) thick and of mass per unit area 300 kg/m ² (min)?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
3.	Are inner leaves to external (flanking) walls of the correct block density?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
4.	Are joints between precast concrete planks grouted and sealed?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
5.	Are precast concrete planks built into the masonry walls?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
6.	Is the IsoEdge flanking strip installed for all room perimeters?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
7.	Are the Isorubber joints overlapped by 50mm and sealed with tape?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
8.	Is the Isorubber layer overlapping the IsoEdge flanking strip?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
9.	Are the skirting boards isolated from the screed by the IsoEdge flanking strip?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
10.	Are all ceiling board joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
11.	Are service pipes wrapped in quilt and boxed in with two layers of nominal 8 kg/m ² gypsum-based board?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>
12.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input style="width: 100%;" type="text"/>

Contact details for technical assistance from Thermal Economics, manufacturer of Isorubber resilient layer system:
Telephone: 01582 544255 Fax: 01582 429305 E-mail: technical@thermal-economics.co.uk

Notes (include details of any corrective action)


Site manager/supervisor signature

©: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Precast concrete plank ■
Screed laid on Thermal Economics 6mm Isorubber Base layer ■




Sketch shows CT0 type ceiling treatment

Screed	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m ² mass per unit area
Resilient layer	6mm Isorubber Base layer with IsoEdge flanking strip
Structural floor	Precast concrete plank of 150mm (min) thickness and 300 kg/m ² (min) mass per unit area
Ceiling	See section 3 for suitable ceiling treatment
Absorbent material	50mm (min) mineral wool quilt insulation 10 kg/m ³ (min)

SYSTEM INSTALLATION

The use of this screed resilient layer system **must** incorporate the following:

- 1) **6mm Isorubber Base layer**
(resilient layer to be laid over entire floor area with minimum 50mm overlaps)
- 2) **IsoEdge** flanking strip
- 3) All joints taped




- **IsoEdge** flanking strip to be installed at all room perimeters. See manufacturer's guidance.
- See Section 4 for acceptable installation alternatives for 40mm proprietary screeds

Robust Details Limited can only accept registration of this floor once the builder agrees to receive training from Thermal Economics on the installation of the screed and resilient layer. Please contact Robust Details Limited for further information.

DO


- Butt planks tightly together
- Grout all joints between planks
- Fill all voids between walls and floor
- Ensure 6mm Isorubber resilient layer is laid over the entire floor surface and has overlapped joints of 50mm sealed with tape. On no account should the screed come into contact with the floor slab. (see Section 4 for 40mm proprietary screeds)
- Ensure 6mm Isorubber overlaps with IsoEdge flanking strip. On no account should screed come into contact with floor slab or perimeter walls
- Ensure the IsoEdge flanking strip isolates the skirting and wall linings. On no account should screed come into contact with the wall lining and skirting
- Ensure that only the correct blocks are used in the construction of external (flanking) walls, unless specifically referred to in the Handbook all blocks should be assumed to be solid (i.e. not hollow or cellular)
- Make sure ceiling treatment is installed in accordance with the manufacturer's instructions

1. External (flanking) wall junction



Sketch shows CT0 type ceiling treatment

2. Separating wall junction







Sketch shows CT0 type ceiling treatment

3. Ceiling treatments for E-FC-14

All ceiling treatments must be installed in accordance with the manufacturer's instructions. All ceiling joints must be sealed with tape or caulked with sealant.

Ensure IsoSonic cleats are fitted with the pads against the concrete planks



Downlighters and recessed lighting

Provided there is a minimum ceiling void as stated below for CT0, CT1 or CT2, downlighters or recessed lighting may be installed in the ceiling:

- in accordance with the manufacturer's instructions
- at no more than one light per 2m² of ceiling area in each room or see Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety

CT0 – Metal ceiling system - 150mm void

To be used for 150mm (min) depth concrete planks

- any metal ceiling frame, suspended from IsoSonic cleats
- 50mm (min) mineral wool quilt insulation 10 kg/m³ (min)
- one layer 15mm (nominal 10 kg/m²) gypsum-based board

CT1 – Metal ceiling system - 100mm void

Only to be used for 200mm (min) depth concrete planks


- any metal ceiling frame, suspended from IsoSonic cleats
- 50mm (min) mineral wool quilt insulation 10 kg/m³ (min)
- one layer 15mm (nominal 10 kg/m²) gypsum-based board

CT2 – Timber battens and counterbattens with IsoSonic Hangers Type C. Only to be used for 200mm (min) depth concrete planks

Only to be used for 200mm (min) depth concrete planks

- 50x50mm softwood battens
- 50x50mm counterbattens
- IsoSonic Hangers Type C
- 50mm (min) mineral wool quilt insulation 10 kg/m³ (min)
- one layer 15mm (nominal 10 kg/m²) gypsum-based board


4. Resilient layer installation for different screed types



SCREED TYPE

65mm (min) cement:sand screed

- Isorubber layer joints to be overlapped by 50mm (min)
- Upper Isorubber layer edge joints to be sealed by tape



SCREED TYPE

40mm (min) proprietary screed


- Isorubber layer joints to be butt jointed
- Isorubber layer joints to be sealed by tape
- Polythene layer to be laid over whole floor overlapping joints

5. Underfloor heating systems within screeds


Underfloor heating systems (including connectors and fixings) installed within the screed must not penetrate the resilient layer or bridge the screed to the slab.

Underfloor heating systems which have a supporting layer/board may be laid on top of the Isorubber.

Appropriate screed depth cover to the heating system must be designed for – contact underfloor heating manufacturer for guidance.



6. Services – Service pipes through separating floor



Sketch shows CT0 type ceiling treatment

CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Has training been received from Thermal Economics?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Are precast concrete planks 150mm (min) thick and of mass per unit area 300 kg/m ² (min)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are inner leaves to external (flanking) walls of the correct block density?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Are joints between precast concrete planks grouted and sealed?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Are precast concrete planks built into the masonry walls?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Is the IsoEdge flanking strip installed for all room perimeters?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Are the Isorubber layer joints overlapped by 50mm and sealed with tape?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Is the Isorubber layer overlapping the IsoEdge flanking strip?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Are the skirting boards isolated from the screed by the IsoEdge flanking strip?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are the IsoSonic cleats installed with the pads against the precast planks?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Is IsoSonic ceiling strip installed at ceiling perimeters?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Is 50mm (min) mineral wool quilt insulation 10 kg/m ³ (min) installed in the ceiling void?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
13.	Are all ceiling board joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
14.	Are service pipes wrapped in quilt and boxed in with two layers of nominal 8 kg/m ² gypsum-based board?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
15.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Contact details for technical assistance from Thermal Economics, manufacturer of Isorubber resilient layer system:
Telephone: 01582 544255 Fax: 01582 429305 E-mail: technical@thermal-economics.co.uk


Notes (include details of any corrective action)
 Site manager/supervisor signature

©: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

- Insitu concrete slab with flat soffit
- For use in reinforced concrete frame construction
- Bonded resilient floor covering, or screed laid on resilient layer system



Screed	65mm (min) cement:sand screed or 40mm (min) proprietary screed of nominal 80 kg/m ² mass per unit area
Resilient layer	See list below and section 7, or see section 8 for bonded resilient floor coverings
Structural floor	225mm (min) insitu concrete floor slab, 2400 kg/m ³ (min) density without screed
Ceiling	See section 9 for suitable ceiling treatment

Reinforced concrete frame construction - alternative external (flanking) wall construction

Storey height glazing units and external insulated cladding panels are an acceptable alternative to the cavity walls illustrated provided:

- Glazing units should not be continuous between storeys
- Mullion or transom supports/framing should not be continuous between dwellings
- Refer to Appendix A

Under-screed Resilient Layer systems

Only the following under-screed Resilient Layer systems may be used on E-FC-18 (see also Section 7):

- Thermal Economics Isorubber Base and IsoEdge Flanking Strip
- *Collecta*® *YELOfon*® HD10+ and E-strip
- Icopal-MONARFLOOR® TRANQUILT® system
- Thermal Economics Isorubber HP3 and IsoEdge Flanking Strip
- InstaCoustic InstaLay 65
- Regupol Quietlay


When using under-screed resilient layer systems:

- Ensure resilient layer is laid over the entire floor surface and has overlapped joints appropriately sealed with tape
- Ensure resilient layer overlaps with flanking strip and is taped and sealed at joints. On no account should the screed come into contact with the floor slab or perimeter walls
- Ensure the flanking strip isolates the skirting and wall linings. On no account should the screed come into contact with the wall lining and skirting
- Refer to Section 7 for details of installation, and requirements for proprietary screeds
- Refer to Appendix A


Bonded Resilient floor coverings

Refer to Section 8 for bonded resilient floor covering requirements


1. External (flanking) wall junction – lightweight external



2. External (flanking) wall junction – masonry outer leaf



Timber I-Joists ■
Use with timber frame walls only ■




Floating floor	See section 6 for suitable floating floor treatment
Floor decking	15mm thick (min) wood based board, density 600 kg/m ³ (min)
Joists	235mm (min) timber I-Joists
Absorbent material	100mm (min) mineral wool quilt insulation (10–36 kg/m ³) or Collecta MICRO 50 between joists
Ceiling	See section 5 for suitable ceiling treatment

Note: Structural framing details may vary slightly between different manufacturers and this is permitted, however, all dimension specifications within this Robust Detail must be adhered to.


DO

- Lay quilt between all joists, including doubled up I-joists, ensuring no gaps remain
- Ensure floating floor treatment is suitable and is installed in accordance with the manufacturer's instructions
- Ensure quilt is laid between and not under flooring battens
- Install flanking strips around the perimeter of the flooring board to isolate floor from walls and skirtings
- Ensure resilient ceiling bars are fixed at right angles to the joists
- Ensure timber floor ceiling treatment is either CT1, CT2 or CT3 and is fixed correctly (see page 4)
- Stagger joints in ceiling layers
- Refer to Appendix A



1. External (flanking) wall junction





2. Separating wall junction




3. Internal wall junction (non loadbearing)



4. Internal wall junction (loadbearing)



Alternative detail



5. Ceiling treatment for E-FT-1

Timber floor ceiling treatment must be either CT1, CT2 or CT3 (see below). All joints to outer layers of ceiling must be sealed with tape or caulked with sealant.

The maximum load on resilient bars should not exceed that specified in the manufacturer's instructions.

Ensure ceiling layers have staggered joints.

Services must not puncture ceiling linings (except cables, which should be sealed around with flexible sealant)


Downlighters and recessed lighting

Downlighters or recessed lighting may be installed in the ceiling:

- in accordance with the manufacturer's instructions
- at no more than one light per 2m² of ceiling area in each room unless the use of a greater density of light fittings is supported by testing undertaken in accordance with Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety

Note: Only downlighters which have been satisfactorily assessed in accordance with the procedure described in Appendix F "Determination of the acoustic performance of downlighters and recessed lighting in timber separating floors" are acceptable.



CEILING BOARD FIXINGS MUST NOT PENETRATE OR TOUCH JOISTS

16mm (min) resilient bars with CT1 and CT2

16mm (min) metal resilient ceiling bars mounted at right angles to the joists at 400mm centres (bars must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 17\text{dB}$ and $rd\Delta L_w = 16\text{dB}$) – see Appendix E

Ceiling treatment CT1

Two layers of gypsum-based board, composed of 19mm (nominal 13.5 kg/m²) fixed with 32mm screws, and 12.5mm (nominal 10 kg/m²) fixed with 42 mm screws

Ceiling treatment CT2

Two layers of gypsum-based boards composed of 15mm (nominal 12.5 kg/m²) fixed with 25mm screws and second layer of 15mm gypsum-based board (nominal 12.5 kg/m²) fixed with 42mm screws

25mm (min) resilient bars with CT3

25mm (min) metal resilient ceiling bars mounted at right angles to the joists at 400mm centres (bars must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 17\text{dB}$ and $rd\Delta L_w = 16\text{dB}$) - see Appendix E


Ceiling treatment CT3

Two layers of gypsum-based board, composed of 10mm (nominal 12kg/m²) fixed with 30mm screws and second layer of 10mm (nominal 12kg/m²) fixed with 30mm screws

6. Floating floor treatment for E-FT-1

Floating floor treatment:

- a) Must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 13\text{dB}$ and $rd\Delta L_w = 15\text{dB}$ - see Appendix C.
 - b) Must be installed in accordance with the manufacturer's instructions.
 - c) Require 5mm (min) resilient flanking strips around the perimeter of the flooring board to isolate floor from walls and skirting.
 - d) For further guidance on floating floor treatments and flanking strips, please refer to Appendix A.
- * Note - void dimension indicated is when floor is loaded to 25 kg/m^2 .




FFT1 – Resilient composite deep batten system for E-FT-1

- 18 mm (min) t&g flooring board
- gypsum-based board nominal 13.5 kg/m^2
- FFT1 resilient composite deep battens
- resilient layer must be continuous and pre-bonded to batten
- battens may have the resilient layer at the top or the bottom
- mineral wool quilt laid between battens
 - 13mm (min) $33\text{-}36\text{ kg/m}^3$, or
 - 25mm (min) $10\text{-}36\text{ kg/m}^3$
 or Collecta MICRO 15
- ensure any services do not bridge the resilient layer

Collecta HiDECK Structural system

- refer to Appendix A3

7. Services – pipes through separating floor



CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are timber I-Joists at least 235mm deep?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Has the specified quilt been fitted between the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are resilient ceiling bars fitted at right angles to the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Has ceiling system been fitted in accordance with the manufacturer’s instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Has floating floor treatment been fitted in accordance with the manufacturer’s instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Has the specified quilt been fitted between the floor battens?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Is ceiling treatment CT1, CT2 or CT3 fixed to the resilient bars with correct screws, such that the screws do not touch or penetrate the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Are all joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Are vertical service pipes wrapped in quilt and boxed in with two layers of gypsum-based board combined nominal mass per unit area of 16 kg/m²?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Have all resilient flanking strips been fitted?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Notes (include details of any corrective action)


Site manager/supervisor signature

©: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Timber Solid Joists ■
Use with timber frame walls only ■



Floating floor	See section 6 for suitable floating floor treatment
Floor decking	11mm thick (min) wood based board, density 600 kg/m ³ (min) or Walker Timber perforated deck system
Joists	220mm (min) solid timber joists at maximum 400mm centres
Absorbent material	100mm (min) mineral wool quilt insulation (10–36 kg/m ³) or Collecta MICRO 50 between joists
Ceiling	See section 5 for suitable ceiling treatment

For wider joist centres

Joist spacings may be increased to maximum 600mm centres provided:


- joist depth is 240mm (min) and
- floor decking is minimum 15mm thick

Note: Structural framing details may vary slightly between different manufacturers and this is permitted, however, all dimension specifications within this Robust Detail must be adhered to.


DO

- Lay quilt between joists ensuring no gaps remain
- Ensure floating floor treatment is suitable and is installed in accordance with the manufacturer's instructions
- Ensure sub-deck quilt is laid between and not under flooring battens
- Install flanking strips around the perimeter of the flooring board to isolate floor from walls and skirtings
- Ensure resilient ceiling bars are fixed at right angles to the joists
- Ensure timber floor ceiling treatment is either CT1, CT2 or CT3 and is fixed correctly (see page 4)
- Stagger joints in ceiling layers
- Refer to Appendix A



1. External (flanking) wall junction





2. Separating wall junction




3. Internal wall junction (non loadbearing)



4. Internal wall junction (loadbearing)



Alternative detail



5. Ceiling treatment for E-FT-2

Timber floor ceiling treatment must be either CT1, CT2 or CT3 (see below). All joints to outer layers of ceiling must be sealed with tape or caulked with sealant.

The maximum load on resilient bars should not exceed that specified in the manufacturer's instructions.

Ensure ceiling layers have staggered joints.

Services must not puncture ceiling linings (except cables, which should be sealed around with flexible sealant)


Downlighters and recessed lighting

Downlighters or recessed lighting may be installed in the ceiling:

- in accordance with the manufacturer's instructions
- at no more than one light per 2m² of ceiling area in each room unless the use of a greater density of light fittings is supported by testing undertaken in accordance with Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety

Note: Only downlighters which have been satisfactorily assessed in accordance with the procedure described in Appendix F "Determination of the acoustic performance of downlighters and recessed lighting in timber separating floors" are acceptable.



CEILING BOARD FIXINGS MUST NOT PENETRATE OR TOUCH JOISTS

16mm (min) resilient bars with CT1 and CT2

16mm (min) metal resilient ceiling bars mounted at right angles to the joists at 400mm centres (bars must achieve a minimum laboratory performance of $rd\Delta Rw+C_{tr}=17dB$ and $rd\Delta Lw=16dB$) – see Appendix E

Ceiling treatment CT1

Two layers of gypsum-based board, composed of 19mm (nominal 13.5 kg/m²) fixed with 32mm screws, and 12.5mm (nominal 8 kg/m²) fixed with 42 mm screws

Ceiling treatment CT2

Two layers of gypsum-based boards composed of 15mm (nominal 12.5 kg/m²) fixed with 25mm screws and second layer of 15mm gypsum-based board (nominal 12.5 kg/m²) fixed with 42mm screws

25mm (min) resilient bars with CT3

25mm (min) metal resilient ceiling bars mounted at right angles to the joists at 400mm centres (bars must achieve a minimum laboratory performance of $rd\Delta Rw+C_{tr}=17dB$ and $rd\Delta Lw=16dB$) - see Appendix E


Ceiling treatment CT3

Two layers of gypsum-based board, composed of 10mm (nominal 12 kg/m²) fixed with 30mm screws and second layer of 10mm (nominal 12 kg/m²) fixed with 30mm screws

6. Floating floor treatment for E-FT-2

Floating floor treatment:

- a) Must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 13\text{dB}$ and $rd\Delta L_w = 15\text{dB}$ - see Appendix C.
 - b) Must be installed in accordance with the manufacturer's instructions.
 - c) Require 5mm (min) resilient flanking strips around the perimeter of the flooring board to isolate floor from walls and skirting.
 - d) For further guidance on floating floor treatments and flanking strips, please refer to Appendix A.
- * Note - void dimension indicated is when floor is loaded to 25 kg/m^2 .




FFT1 – Resilient composite deep batten system for E-FT-2

- 18 mm (min) t&g flooring board
- gypsum-based board nominal 13.5 kg/m^2
- FFT-1 resilient composite deep battens
- resilient layer must be continuous and pre-bonded to batten
- battens may have the resilient layer at the top or the bottom
- 60mm (min) $10\text{-}36\text{ kg/m}^3$ mineral wool quilt laid between battens
- ensure any services do not bridge the resilient layer

Collecta HiDECK Structural system

- refer to Appendix A3

7. Services – pipes through separating floor



CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are solid timber joists at least 220mm deep, or at least 240mm deep if joists installed at greater than 400mm centres?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Has the specified quilt been fitted between the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are resilient ceiling bars fitted at right angles to the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Has ceiling system been fitted in accordance with the manufacturer's instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Is floor decking 11mm thick (min); or 15mm thick (min) if joists at greater than 400mm centres?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Has floating floor treatment been fitted in accordance with the manufacturer's instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Has the specified quilt been fitted between the floor battens?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Is ceiling treatment CT1, CT2 or CT3 fixed to the resilient bars with correct screws such that the screws do not touch or penetrate the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Are all joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are vertical service pipes wrapped in quilt and boxed in with two layers of gypsum-based board combined nominal mass per unit area of 16 kg/m ² ?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Have all resilient flanking strips been fitted?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Notes (include details of any corrective action)


Site manager/supervisor signature

©: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Timber flange and metal web joists ■
 Use with timber frame walls only ■



Floating floor	See section 10 for suitable floating floor treatment
Floor decking	18mm thick (min) wood based board, density min 600 kg/m ³
Joists	253mm (min) metal web joists (see joist type below)
Absorbent material	100mm (min) mineral wool quilt insulation (10–36 kg/m ³) or Collecta MICRO 50 between joists
Ceiling	See section 9 for suitable ceiling treatment

Joist type

IMPORTANT

Only the following metal web joists may be used in E-FT-3:

- MiTek Posi-Joist
- Prestoplan PresWeb
- WOLF easi-joist
- ITW Gang-Nail Ecojoist
- ITW Alpine SpaceJoist

Notes:


Although single header and sole plates are indicated, increasing the number of header and sole plates would be acceptable, however, all dimension specifications within this Robust Detail must be adhered to.

Metal web joists can be **top chord/flange** supported or **fully built-in** and supported on the panel and this is permitted, however, all dimension specifications within this Robust Detail must be adhered to.


DO

- Ensure correct metal web joists are being used (see joist type)
- Lay quilt between joists ensuring no gaps remain
- Ensure floating floor treatment is suitable and is installed in accordance with the manufacturer's instructions (See page 7)
- Ensure quilt within floating floor is laid between and not under flooring battens
- Install resilient flanking strips around the perimeter of the flooring board to isolate floor from walls and skirtings
- Ensure resilient ceiling bars are fixed at right angles to the joists
- Ensure timber floor ceiling treatment is fixed correctly (see page 6)
- Stagger joints in ceiling layers
- Refer to Appendix A


1. External (flanking) wall junction (top chord supported)




2. External (flanking) wall junction (fully built-in)



3. Separating wall junction (top chord supported)




- If using **robustdetails**[®] for wall - refer to Table 3b in introduction to select an appropriate **robustdetails**[®] separating wall
- If using wall requiring pre-completion testing - seek specialist advice
- Two layers gypsum-based board total nominal mass per unit area 22 kg/m² both sides
- 5mm (min) resilient flanking strip
- Softwood timber infill between supporting top chords/flanges of joists
- Joists may span in either direction
- Ring beams packed to stud width
- Close cavity with a cavity stop (see Appendix A)
- Softwood timber noggings for resilient bar support (leave a small gap at end of resilient bar)
- Seal all perimeter joints with tape or caulk with sealant




Alternative detail

4. Separating wall junction (fully built-in)




- If using **robustdetails**[®] for wall - refer to Table 3b in introduction to select an appropriate **robustdetails**[®] separating wall
- If using wall requiring pre-completion testing - seek specialist advice
- Two layers gypsum-based board total nominal mass per unit area 22 kg/m² both sides
- 5mm (min) resilient flanking strip
- Close spaces between floor joists with full depth timber blocking or continuous header joist where joists are at right angles to the wall
- Joists may span in either direction
- Close cavity with a cavity stop (see Appendix A)
- Softwood timber noggings for resilient bar support (leave a small gap at end of resilient bar)
- Seal all perimeter joints with tape or caulk with sealant



Alternative detail

5. Non loadbearing internal wall perpendicular to joists



Seal all perimeter joints with tape or caulk with sealant

Where required internal wall to comply with Building Regulations Requirement E2


5mm (min) resilient flanking strip

Floating floor

Metal web joist (see joist type, page 1)

*Note - non loadbearing partitions may also be taken directly off the floating floor treatment, check with manufacturer's instructions for installation (see Appendix A)

6. Non loadbearing internal wall parallel to joists



5mm (min) resilient flanking strip


Extra metal web joist (see joist type, page 1) under internal wall

Floor decking

Softwood timber noggings for resilient bar support (leave a small gap at end of resilient bar)


Seal all perimeter joints with tape or caulk with sealant

*Note - non loadbearing partitions may also be taken directly off the floating floor treatment, check with manufacturer's instructions for installation (see Appendix A)




Alternative detail



7. Loadbearing internal wall perpendicular to joists



Alternative detail



8. Loadbearing internal wall parallel to joists



9. Ceiling treatment for E-FT-3

Timber floor ceiling treatment must be either CT1, CT2 or CT3 (see below). All joints to outer layers of ceiling must be sealed with tape or caulked with sealant.

The maximum load on resilient bars should not exceed that specified in the manufacturer's instructions.

Ensure ceiling layers have staggered joints.

Services must not puncture ceiling linings (except cables, which should be sealed around with flexible sealant)


Downlighters and recessed lighting

Downlighters or recessed lighting may be installed in the ceiling:

- in accordance with the manufacturer's instructions
- at no more than one light per 2m² of ceiling area in each room unless the use of a greater density of light fittings is supported by testing undertaken in accordance with Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety

Note: Only downlighters which have been satisfactorily assessed in accordance with the procedure described in Appendix F "Determination of the acoustic performance of downlighters and recessed lighting in timber separating floors" are acceptable.



CEILING BOARD FIXINGS MUST NOT PENETRATE OR TOUCH JOISTS

16mm (min) resilient bars with CT1 and CT2

16mm (min) metal resilient ceiling bars mounted at right angles to the joists at 400mm centres (bars must achieve a minimum laboratory performance of $rd\Delta Rw+C_{tr}=17dB$ and $rd\Delta Lw=16dB$) – see Appendix E

Ceiling treatment CT1

Two layers of gypsum-based board, composed of 19mm (nominal 13.5 kg/m²) fixed with 32mm screws, and 12.5mm (nominal 10 kg/m²) fixed with 42 mm screws

Ceiling treatment CT2

Two layers of gypsum-based boards composed of 15mm (nominal 11.7 kg/m²) fixed with 25mm screws and second layer of 15mm gypsum-based board (nominal 11.7 kg/m²) fixed with 42mm screws

25mm (min) resilient bars with CT3

25mm (min) metal resilient ceiling bars mounted at right angles to the joists at 400mm centres (bars must achieve a minimum laboratory performance of $rd\Delta Rw+C_{tr}=17dB$ and $rd\Delta Lw=16dB$) - see Appendix E


Ceiling treatment CT3

Two layers of gypsum-based board, composed of 10mm (nominal 12kg/m²) fixed with 30mm screws and second layer of 10mm (nominal 12kg/m²) fixed with 30mm screws

10. Floating floor treatment for E-FT-3

Floating floor treatment:

- Must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 13\text{dB}$ and $rd\Delta L_w = 15\text{dB}$ - see Appendix C.
 - Must be installed in accordance with the manufacturer's instructions.
 - Require 5mm (min) resilient flanking strips around the perimeter of the flooring board to isolate floor from walls and skirting.
 - For further guidance on floating floor treatments and flanking strips, please refer to Appendix A.
- * Note - void dimension indicated is when floor is loaded to 25 kg/m^2 .



FFT1 – Resilient composite deep batten system for E-FT-3


- 18 mm (min) t&g flooring board
- gypsum-based board nominal 13.5 kg/m^2
- FFT1 resilient composite deep battens
- battens may have the resilient layer at the top or the bottom
- mineral wool quilt laid between battens
 - 13mm (min) $33\text{-}36\text{ kg/m}^3$, or
 - 25mm (min) $10\text{-}36\text{ kg/m}^3$
 - or Collecta MICRO 15
- ensure any services do not bridge the resilient layer

* Note - Services may run within the floor zone (see Appendix A)

Collecta HiDECK Structural system

- refer to Appendix A3

11. Services – pipes through separating floor



Section

Alternative detail

Sketch shows top chord supported external (flanking) wall junction detail, for fully built-in arrangement see section 2

CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____


Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are correct metal web joists being used (see page 1 of Robust Detail)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Which of the permitted metal web joist types are being used?	<input type="text"/>		
3.	Are joists at least 253mm deep?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Has the specified quilt been fitted between the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Are resilient ceiling bars fitted at right angles to the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Has ceiling system been fitted in accordance with the manufacturer's instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Has floating floor treatment been fitted in accordance with the manufacturer's instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Has the specified quilt been fitted between the floor battens?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Is ceiling treatment CT1, CT2 or CT3 fixed to the resilient bars with correct screws such that the screws do not touch or penetrate the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are all joints to gypsum-based boards sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Are vertical service pipes wrapped in quilt and boxed in with two layers of gypsum-based board combined nominal mass per unit area of 16 kg/m ² ?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Have all resilient flanking strips been fitted?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
13.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Notes (include details of any corrective action)

Site manager/supervisor signature

©: UK registered trade mark no. 2291665
 © Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.
 Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

- *Collecta*® ScreedBoard® 28 on timber sub-floor
- Timber I-Joists
- Use with timber frame walls only




Floating floor	<i>Collecta</i> ® ScreedBoard® 28
Floor decking	18mm thick (min) wood based board, density 600 kg/m ³ (min)
Joists	240mm (min) timber I-joist
Absorbent material	100mm (min) mineral wool quilt insulation (10–36 kg/m ³) or <i>Collecta</i> MICRO 50 between joists
Ceiling	See section 5 for ceiling treatment

Note: Structural framing details may vary slightly between different manufacturers and this is permitted, however, all dimension specifications within this Robust Detail must be adhered to.


DO

- Lay quilt (min 100mm thick) between all joists, including doubled up timber I-joists, ensuring no gaps remain
- Apply *Collecta*® SB adhesive to all ScreedBoard® 28 decking joints
- Install *Collecta*® YELOfon® FS50 flanking angle around the perimeter of the ScreedBoard® 28 to isolate floor from walls and skirtings
- Ensure resilient ceiling bars are fixed at right angles to the joists
- Ensure ceiling treatment is fixed correctly (see section 5)
- Stagger joints in ceiling layers
- Refer to Appendix A


1. External (flanking) wall junction



2. Separating wall junction




6. Underfloor heating systems below ScreedBoard®



Section

7. Services – pipes through separating floor



Section

CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are timber I-joists minimum 240mm deep?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Is sub-deck minimum 18mm, 600 kg/m ³ ?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are YELOfon® FS50 flanking angles installed correctly?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Has the ScreedBoard® 28 floating floor treatment been fitted in accordance with the manufacturer’s instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Where underfloor heating is used, is FIBREfon® 8 installed in addition to the ScreedBoard® 20?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Are the correct type of resilient ceiling bars used and fitted, in accordance with the manufacturer’s instructions, at right angles to the joists (Collecta® HP30 bars must be used if second ceiling is not included)?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Has the specified quilt been fitted between the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Are the ceiling treatments fixed to the resilient bars with correct screws, such that the screws do not touch or penetrate the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	For CT1 or CT2 is secondary ceiling void minimum 150mm?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Are all joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Are vertical service pipes wrapped in quilt and boxed in with two layers of gypsum-based board combined nominal mass per unit area of 16 kg/m ² ?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
12.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Contact details for technical assistance from *Collecta*®, manufacturer of ScreedBoard® 28 system:
Telephone: 01634 296677 Fax: 01634 226630 E-mail: technical@collecta.co.uk

Notes (include details of any corrective action)


Site manager/supervisor signature

®: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Hadley Group UltraBEAM Metal Joists ■
 Use with lightweight metal frame walls only ■




Floating floor	See section 6 for suitable floating floor treatment
Floor decking	22mm thick (min) wood based board, density 600 kg/m ³ (min)
Joists	225mm (min) deep UltraBEAM metal joists
Absorbent material	100mm (min) mineral wool quilt insulation (10–36 kg/m ³) or Collecta MICRO 50 between joists
Ceiling	See section 5 for suitable ceiling treatment


DO

- Lay quilt between all joists, including doubled up joists, ensuring no gaps remain
- Ensure floating floor treatment is suitable and is installed in accordance with the manufacturer's instructions
- Ensure quilt is laid between and not under flooring battens
- Install flanking strips around the perimeter of the flooring board to isolate floor from walls and skirtings
- Ensure resilient ceiling bars are fixed at right angles to the joists
- Ensure ceiling treatment is fixed correctly (see page 4)
- Stagger joints in ceiling layers
- Refer to Appendix A


1. External (flanking) wall junction – masonry outer leaf




2. External (flanking) wall junction – timber cladding outer leaf



3. Separating wall junction



4. Internal wall junction



5. Ceiling treatment for E-FS-2

Metal floor ceiling treatment must be as shown below. All joints to outer layers of ceiling must be sealed with tape or caulked with sealant.

The maximum load on resilient bars should not exceed that specified in the manufacturer's instructions.

Ensure ceiling layers have staggered joints.

Services must not puncture ceiling linings (except cables, which should be sealed around with flexible sealant)


Downlighters and recessed lighting

Downlighters or recessed lighting may be installed in the ceiling:

- in accordance with the manufacturer's instructions
- at no more than one light per 2m² of ceiling area in each room unless the use of a greater density of light fittings is supported by testing undertaken in accordance with Appendix F
- at centres not less than 0.75m
- into openings not exceeding 100mm diameter or 100x100mm

Particular attention should also be paid to Building Regulations Part B - Fire Safety

Note: Only downlighters which have been satisfactorily assessed in accordance with the procedure described in Appendix F "Determination of the acoustic performance of downlighters and recessed lighting in lightweight separating floors" are acceptable.



CEILING BOARD FIXINGS MUST NOT PENETRATE OR TOUCH JOISTS

16mm (min) resilient bars with CT1 and CT2

16mm (min) metal resilient ceiling bars mounted at right angles to the joists at 450mm centres (bars must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 17\text{dB}$ and $rd\Delta L_w = 16\text{dB}$) – see Appendix E

Ceiling treatment CT1

Two layers of gypsum-based board, composed of 19mm (nominal 13.5 kg/m²) fixed with 32mm screws, and 12.5mm (nominal 10 kg/m²) fixed with 42 mm screws

Ceiling treatment CT2

Two layers of gypsum-based boards composed of 15mm (nominal 12.5 kg/m²) fixed with 25mm screws and second layer of 15mm gypsum-based board (nominal 12.5 kg/m²) fixed with 42mm screws

25mm (min) resilient bars with CT3

25mm (min) metal resilient ceiling bars mounted at right angles to the joists at 450mm centres (bars must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 17\text{dB}$ and $rd\Delta L_w = 16\text{dB}$) - see Appendix E


Ceiling treatment CT3

Two layers of gypsum-based board, composed of 10mm (nominal 12kg/m²) fixed with 30mm screws and second layer of 10mm (nominal 12kg/m²) fixed with 30mm screws

6. Floating floor treatment for E-FS-2

Floating floor treatment:

- Must achieve a minimum laboratory performance of $rd\Delta R_w + C_{tr} = 13\text{dB}$ and $rd\Delta L_w = 15\text{dB}$ - see Appendix C.
 - Must be installed in accordance with the manufacturer's instructions.
 - Require 5mm (min) resilient flanking strips around the perimeter of the flooring board to isolate floor from walls and skirting.
 - For further guidance on floating floor treatments and flanking strips, please refer to Appendix A.
- * Note - void dimension indicated is when floor is loaded to 25 kg/m².




FFT1 – Resilient composite deep batten system

- 22 mm (min) t&g flooring board
- gypsum-based board nominal 13.5 kg/m²
- FFT1 resilient composite deep battens
- resilient layer must be continuous and pre-bonded to batten
- battens may have the resilient layer at the top or the bottom
- mineral wool quilt laid between battens
 - 13mm (min) 33-36 kg/m³, or
 - 25mm (min) 10-36 kg/m³
 - or Collecta MICRO 15
- ensure any services do not bridge the resilient layer

Collecta HiDECK Structural system

- refer to Appendix A3

7. Services – pipes through separating floor



CHECKLIST (to be completed by site manager/supervisor)

Company: _____

Site: _____

Plot: _____ Site manager/supervisor: _____

Ref.	Item	Yes (✓)	No (✓)	Inspected (initials & date)
1.	Are UltraBEAM metal joists at least 225mm deep?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
2.	Has the specified quilt been fitted between the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
3.	Are resilient ceiling bars fitted at right angles to the joists?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
4.	Has ceiling system been fitted in accordance with the manufacturer’s instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
5.	Has floating floor treatment been fitted in accordance with the manufacturer’s instructions?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
6.	Has the specified quilt been fitted between the floor battens?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
7.	Is ceiling treatment fixed to the resilient bars with correct screws?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
8.	Are all joints sealed with tape or caulked with sealant?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
9.	Are vertical service pipes wrapped in quilt and boxed in with two layers of gypsum-based board combined nominal mass per unit area of 20 kg/m ² ?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
10.	Have all resilient flanking strips been fitted?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>
11.	Is separating floor satisfactorily complete?	<input type="checkbox"/>	<input type="checkbox"/>	<input type="text"/>

Contact details for technical assistance from Hadley Group, manufacturer of UltraBEAM metal joists:
Telephone: 0121 555 1300 Fax: 0121 555 1301 E-mail: info@hadleygroup.co.uk

Notes (include details of any corrective action)

Site manager/supervisor signature

©: UK registered trade mark no. 2291665

© Robust Details Limited 2011. All rights reserved. No part of this Handbook (other than the checklists) may be reproduced in any material form or issued or communicated to the public (including photocopying or storing it in any medium by electronic means, and whether or not transiently or incidentally to some other use of this Handbook) without the prior written permission of Robust Details Limited except in accordance with the provisions of the Copyright, Designs and Patents Act 1988.

Warning: the doing of an unauthorised act in relation to a copyright work may result in both a civil claim for damages and criminal prosecution.

Appendix A3 – Specific Proprietary Products



Contents

Section	Page
British Gypsum GypFloor SB floating floor treatment for robust details® concrete separating floors	2
Insumate Limited insulation support tray for robust details® timber joist separating floors	3
Collecta HiDECK Structural floor board floating floor treatment for robust details® timber and steel joist separating floors	4



Appendix A3 – Specific Proprietary Products

British Gypsum GypFloor SB floating floor treatment for **robustdetails®** concrete separating floors. Refer to Table 7 in Introduction.

Floating floor treatment 1 – 70mm



Floating floor treatment 2 – 50mm



Key

- 1 British Gypsum 70 SB 65 steel batten.
- 2 British Gypsum 50 SB 65 steel batten.

- a **robustdetails®** concrete separating floor.
- b 18mm (min) t&g flooring board.

Note: The **robustdetails®** separating floor may require a levelling screed. Please refer to the relevant floor details in the Handbook.

This system must be installed in accordance with the manufacturer's instructions.

Gypframe GypFloor SB flanking strip SB3 must be applied around the perimeter of the flooring board to isolate floor from walls and skirting.

For further guidance on floating floor treatments and flanking strips, please refer to Appendix A1.

Contact details for British Gypsum Limited:

Telephone: 08705 456 123


Fax: 08705 456 356

E-mail: bgtechnical.enquiries@bpb.com


Web: www.british-gypsum.com

Appendix A3 – Specific Proprietary Products


Insumate insulation support tray for **robustdetails**® timber joist separating floors.
Refer to Table 7 in Introduction and the relevant Robust Details for acceptable joist types.



Option 1
as illustrated above



Option 2
Insumate trays may be inverted



Key

- 1 Insumate insulation support tray.
 - a Floating floor treatment.
 - b Floor sub-deck.
 - c Absorbent material.
 - d Floor joist – Refer also to Table 7 in Introduction.
 - e Ceiling treatment.
- (For specification of items a to e, refer to the relevant Robust Detail)

Note

Ensure absorbent material 'c' is fitted between all joists, and also between the final joist and the perimeter blocking.



Insumate must be installed in accordance with the manufacturer's instructions.

Contact details for Insumate Limited:


Telephone: 01768 866 009
Fax: 01768 866 009
E-mail: sales@insumateltd.com
Web: www.insumateltd.com

Appendix A3 – Specific Proprietary Products

Collecta HiDECK Structural floor board floating floor treatment for **robustdetails®** timber and steel joist separating floors. Refer to Table 7 in Introduction and the relevant Robust Details for acceptable joist types.



Optional underfloor heating



Partition may be fitted through or on top of the HiDECK Structural floor board

Key

- | | |
|--|--|
| <p>1 25, 28 or 30mm tongue & groove Collecta HiDECK Structural floor board.</p> <p>2 Collecta DECKfon Batten 70.</p> <p>3 5mm Collecta YELOfon ES5 edging strip to the whole flooring perimeter.</p> | <p>a 15mm Collecta FIBREfon Micro 15, or mineral wool - as relevant Robust Detail.</p> <p>b 50mm Collecta FIBREfon Micro 50, or mineral wool - as relevant Robust Detail.</p> <p>c Steel or timber joist - as relevant Robust Detail.</p> <p>d Timber subdeck - as relevant Robust Detail.</p> <p>e Ceiling treatment - as relevant Robust Detail.</p> <p>f Optional underfloor heating.</p> |
|--|--|

HiDECK Structural floor board and related components must be fitted in accordance with the manufacturer's instructions.

Contact details for Collecta:

Telephone: 01634 296677
Fax: 01634 226630
E-mail: technical@collecta.co.uk
Web: www.collecta.co.uk